

Muslim Hands MIRPUR

A	Construction of RCC Structure of Mosque and qurn academy having prayer hall of size (18ft7.5inch x 31.75ft), Verandah of size (16'x39.25'), Quran Acadmemy room of size (15ft x 18.75ft),Ablution area of size (15.75ft x 19.5ft) including 3 washrooms with heigh of prayer hall is 11ft.				
S.No	Items & Specification	Quantity	Unit	Unit Rate	Amount
1	Excavation of earthwork for construction of sub structure of Prayer Hall, Quran Academy, boundary wall and Ablution area (365ft length x 3ft Height x 3ft width).	3285	Cft		
2	PCC (365ft length x 3ft width x 0.5ft depth) for substructure of Brick masonay of Prayer Hall, Quran Academy, boundary wall and Ablution area (nominal mix ration 1:3:6) including shuttering, placing, compacting, finishing and curing up to two weeks.(Cement should Bestway Or Fauji)	547.5	Cft		
3	3 inch PCC on floor with 3 inch Brick Ballast for superstructure all rooms,washroom and halls & attached walkway of structure (nominal mix ration 1:3:6) including shuttering, placing, compacting, finishing and curing up to two weeks.(Cement should Bestway Or Fauji)	1100	Cft		
4	All type of 9 inch brick work including 11ft superstructure walls and 2.5 ft brick work in substructure wall with Mortar ratio 1:4, including placing, finishing and curing up to one week (Cement should Bestway Or Fauji with 1st class brick).	3260	Cft		
5	Providing & Fixing of sunny white marble on Ground floor of Prayer Hall, Quran Academy, Ablution area & attached walkway incuding skirting with CSM Ratio 1:4 & Cement grout.(Cement should Bestway Or Fauji)	3,020.00	Sqft		
6	Providing and fixing steel deformed round bars 12mm dia, Grade 60 main bars 6" c/c in both directions, including straightening, cutting, jointing and bending in slabs of prayer hall, Dome, Quran Academy and ablution area , and 5 bars of 12mm dia, Grade 60 main bars in plinth and roof beams & 6 bars of 12mm dia, Grade 60 main bars in structure Columns & 4 bars of 12mm dia, Grade 60 main bars in boundary wall Columns with 6.35mm dia bars 7" c/c as tie & stirrups bars with bend of 8xdiamter of bar at 135.(Islamabd steel recommended) .	#4 (4100kg) + #2 (450kg)	kg		
7	Reinforced cement concrete including shuttering, placing, compacting, finishing and curing upto two weeks(nominal mix ration 1:2:4) for 5 inch slab of prayer hall, Dome, Quran Academy and ablution area, 22 columns of (12"x12"), and 8 columns of boundary wall (9"x9") 365 RFT Plinth of 9"x12" & 278 RFT Door level beams of 9"x12". (Cement should bestway/Fauji).	1,550.00	Cft		
9	Cement plaster in 1:4 CSM 1/2" in internal and external surface of walls including curing, Shuttering complete in all respect (Cement should Bestway Or Fauji)	7,265.00	Sqft		
10	providing and fixing of 6 inch down false Gypsem ceiling using copper wire and steel hooks.	900	Sqft		
12	Providing & fixing of all type of electric work in RCC Structure and also on Main Doors And boundary wall mentioned in drawings including (Wires, lights, 4 ceiling fans, switches etc).	1,658.00	sqft		
15	Providing and fixing 1st class 9 (Fiber doors) sizes of doors are 7ft height and 2ft width, 7ft height and 3.5ft width, 7ft height and 5ft width and 7ft height and 6ft width.	206.50	sqft		
16	Providing & fixing 3 mm Aluminum windows with 5 mm glass fittings.	130	Sqft		
17	Poviding and fixing All type of plumbing work and sanitary fittings including (3 indian seats,3 p traps, 3 mixer sets, 3 accessories set, 3 flush tanks with waste pipe) all items should be of brite company.	1	job		
18	Providing and fixing of safety grills for boundary walls 18 gauge material & pipe should be 1 inchx 1inch for boundary work.Main gate of size 8ftx 6ft.and also roof of verandah with thermopol sheet.	222	sqft		
19	Providing & Laying 1 coat of primer on internal and external surfaces, 2 coat of Silk emulsion on internal surfaces of all walls & 2coat of weather shield on external surface after removing sand particles using regmar/Batti.(Master paints) also on Ceiling. 1 coat of primer & 2 coat of enamel paint on safty grills and Doors(Master paints)	9,000.00	Sqft		
	Total cost				